



Ernakulam Regional Co-operative Milk Producers' Union Limited
Kottayam Dairy, Vadavathoor, Kottayam – 686010.

(An ISO 9001:2015 and ISO 22000:2005 Certified Dairy)

Ph: 04 81 – 2578764, 2578112 E- mail ercmpukdengg@milma.com

GST No 32AAAAAE0621L1Z9

No.KD/Engg/523/2023-24/2116

Dated 01/09/2023

TENDER NOTICE

The Ernakulam Regional Cooperative Milk Producers Union Ltd Invites TENDER from eligible bidders for the tile paving work at KOTTAYAM DAIRY

TERMS AND CONDITION

- 1.Interested eligible bidders may obtain further information from the office of KOTTAYAM DAIRY
- 2.The bid shall be submitted in two cover system consisting of technical bid and price bid .The price bid who qualified the technical bid only will be opened
- 3.Bid validity will be 180 days.
- 4.The bidder should remit an amount of Rs 3500/- as EMD
- 5.The last date for submitting the tender is 15.09.2023 ,1pm and will be opened on same day 3.00PM
- 6.Site can be visited from 2.09.2023 to 14.09.2023 in between office hours
- 7.Time of completion is 90 days after issue of WORK ORDER
- 8.Rate including GST should be quoted
- 9.Work description attached with tender notice
- 10.Tender form costs Rs 250 plus tax

**WORK FOR INTERLOCKING PAVER BLOCK LAYING
WORK IN EXISTING TWO WHEELER PARKING SHED
AND OLD PARLOUR AREA AT KOTTAYAM DAIRY
,VADAVATHOOR**

SL NO	ITEM DESCRIPTION
	EARTH WORK
1	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundation etc. in layers not exceeding 20 cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift up to 1.5 m.
	Existing parlour area filling
2	Filling with contractor's own earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20 cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift up to 1.5 m as per direction of site Engineer-in-charge
	Existing parlour area filling
	CONCRETE WORK
3	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level:1:1:5:3 (1 cement 1.5 coarse sand :3 graded stone aggregate 20 mm nominal size
	RCC BELT ABOVE EXISTING RR RETAINING WALL
	KERB
	EX
4	Centering and shuttering including strutting, propping etc. and removal of form work for: Foundations, footings, bases for columns
	RCC BELT ABOVE EXISTING RR RETAINING WALL
	KERB
	EX
5	Steel reinforcement for R.C.C work including straightening, cutting, bending, placing in position and binding all complete upto plinth level

	Thermo - Mechanically Treated bars of grade Fe-500D or more
	for RCC Belt
	FINISHING WORKS
6	20 mm cement plaster of mix: 1:4 (1 cement : 4 fine sand)
	for RCC Belt
	ROAD WORK
7	Construction of granular sub- base by Providing close graded Material conforming to specifications, mixing in a mechanical mix plant at OMC, Carriage of mixed material by tippers to work site, for all leads & lifts, spreading in uniform layers of specified thickness with motor grader on prepared surface and compacting with vibratory power roller to achieve the desired density, complete as per specifications and directions of Engineer-in- Charge. With Material conforming to Grade - I (size range 75 mm to 0.075 mm) having CBR Value- 30
	Existing parlour area filling
	Two wheeler parking area
8	Providing and laying 80 mm thick factory made cement concrete interlocking paver block of M - 40 grade made by block making machine with strong vibratory compaction, of approved size, design & shape, laid in required colour and pattern over and including 50 mm thick compacted bed of coarse sand, filling the joints with fine sand etc. all complete as per the direction of Engineer-in-charge.
	Existing parlour area filling
	Two wheeler parking area
	MISCELLANEOUS WORKS
9	PCC DISMANTLING
	existing two wheeler parking area

Payment Terms:

- **90% payment on completion of work within 15 days**
- 10% will be retained as performance security. This can be released on submission of a bank guarantee for an equal amount from a nationalised bank. However BG is not submitted the final 10% will be released only after guarantee period

The payment will be made through NEFT/RTGS only



DAIRY MANAGER

KOTTAYAM DAIRY

