

Tender No: .....



**milma**

**ERNAKULAM REGIONAL CO-OPERATIVE MILK PRODUCERS UNION LTD  
THRISSUR DAIRY, RAMAVARMAPURAM - 680 631**

# TENDER

Containing General Conditions of Contract and Schedule for  
**Cloth with Frame - Vinyl - ACP Board - Outlet painting &  
Light Board Works, Hoardings & other Advertisement Works -  
2022-23**

(Tender No. RD/MKTG/601/2022-23/1248 Dated 24-09-2022)

## TENDER DETAILS

Cost of tender form : Rs 236  
EMD for tender : **Rs 5000-00**  
Last date of Tender form Issue : 30-09-2022, Time 11.30 am  
Last date of EMD remitting time : 30-09-2022 12.30pm  
Last Date (Tender submission) : 30-09-2022 1-30 pm  
Opening of tender : 30-09-2022 2-00 pm (Dairy Conference Hall, Thrissur Dairy)

---

SI No	Name of Work	Specifications/Quality	Appox Qty
1	<b>CLOTH BOARD (with Frame and Fixing)</b>	Multi colour digital bio degradable fabric material 240GSM with 4 pass eco solvent print and ¾ inch aluminum beading with insulation. All materials required for carrying out the work shall be provided by the contractor. The work includes supply and erection at designated areas.	30000 Sq Feet
2	<b>Vinyl Stickers Fixing</b>	100 micron vinyl sticker with LDP printing	5000 Sq Feet
3	<b>FOAM VINYL STICERS</b>	100 micron vinyl sticker with LDP printing pasted on 3 mm thick foam board shall be fixed on the wall with lamination.	2500 Sq Feet
4	<b>Vinyl Stickers on containers</b>	100 micron vinyl sticker with LDP printing	1500Sq Feet
5	<b>Vinyl Stickers One way vision Fixing</b>	100 micron vinyl sticker with LDP printing	500 Sq feet
6	<b>ALUMINIUM COMPOSIT PANEL (3mm with acrylic letters with frame and fixing )</b>	ACP having 3mm thickness (Euro board or equivalent) with Acrylic moulded letters without LED 1*x1* GI Sq Pipe Frame angular bracket fixing.	2000 Sq Feet
7	<b>ALUMINIUM COMPOSIT PANEL WITH VINYL LETTERS &amp; Fixing</b>	ACP having 3mm thickness (Euro board or equivalent) with 100 micron vinyl sticker with LDP printing 1x1 GI Sq Pipe Frame angular bracket fixing	1000 Sq Feet
8	<b>ALUMINIUM COMPOSIT PANEL (ACRYLIC WITH LED &amp; FIXING )</b>	ACP having 3mm thickness (Euro board or equivalent) with Acrylic moulded letter 1x1 GI Sq Pipe frame angular bracket fixing front light LED	1500 Sq Feet
9	<b>BACK LIGHT BOARD (SINGLE SIDE &amp; FIXING)</b>	Bio degradable fabric cloth material 240GSM with 4 pass eco solvent print. One inch square tube (GP or GI) box frame with proper fittings. One in aluminum beading, LED tube with quality wires side and back should be covered with 24 gauge GI sheet. All materials required for carrying out the work shall be provided by the contractor. The work included supply and erection at designated areas.	2000 Sq Feet
10	<b>LIGHT BOARD (DOUBLE SIDE &amp; FIXING)</b>	As above with double side vision	2000 Sq Feet
11	<b>LIGHT BOARD (Round)/Glow sign board</b>	0.40 Acrylic, LED LIGHT, VINYLSTICKER, WITH FIXING	150 unit
12	<b>OUTLET PAINTING</b>	Painting with two coat of primer and Enamel paint (Asian Paints) in multi colour as per approved art work and design)	20000 Sq Feet
13	<b>VINYL STCKERS FOR PUFF CONTAINER</b>	100 micro vinyl sticker with LDP painting.	3000 Sq Feet
14	<b>HOARDINGS</b>	Designing Erecting & fixing of Hoarding with240 GSM Cloth with eco solvent 6 pass printing, approx requirement of hoarding erection material :5 inch/4 inch/3 inch channels and 5 inch &2 inch angles.	2000 Sq Feet
15	<b>CLOTH BANNER</b>	200 GSM Cloth with eco solvent printing	1000 Sq Feet
16	<b>LED TV / DIGITAL MENU BOARD</b>	LED TV / DIGITAL MENU BOARD Work as per the requirements	2 Unit